

DELL ROAD- FROM JUST PAST S407 MAIL BOX/ TOP OF HILL TO IRISH RIDGE ROAD THE WORST OF THE ROAD

Dell Rd- from just past S407 mail box/top of hill to Irish Ridge
0.39 miles

Hot Mix Wedge
Left and Right sides going down the hill
Full Width on the bottom
Right Side on the inside of the corner
Left Side on the down hill slope to the top of the hill
Do nothing from the top of the hill to Irish Ridge

Approximately 176 tons

\$20,830

Dell Rd- from Irish Ridge to Short Cut Rd
0.89 miles

Hot Mix Wedge
Right side going down the hill
Full width at the bottom of the hill
Left Side going up the hill, down the hill, and back up the hill
Right Side going down hill ending at Corner View Cabinets
Right Side going down the hill
Left Side going up the hill
Do nothing from top of hill to Short Cut Rd

Approximately 286 tons

\$33,848

SHORT CUT RD- WEGING THE WORST OF THE ROAD

Short Cut Rd- from Dell Rd to County D
0.59 miles

Hot Mix Wedge
Right side, inside corner to the top of the hill ending just past E10833
Left side, as you go up the hill ending just past #10833
Do nothing on the top of the hill
Left and Right side by wood chip pile before E10704
Do nothing for a short section
Left side starting by E10704
Right side going down the hill to bottom
Left side going back up the hill ending at D

Approximately 308 tons

\$36,452

IRISH RIDGE RD- FINISHING OFF THE REST OF THE ROAD NEAR ONEIDA

Irish Ridge Rd- from S554 going up the hill to Oneida Rd
Hot Mix Wedging Right side only

Approximately 44 tons

\$5,207

96,337

159,537

CARY ROAD FROM WOODS RIDGE ROAD TO COUNTY D OPTIONS

Cary Rd- from Woods Ridge to County D

0.70 miles

Single Seal Hard Surface 8" Bar Seal both sides

\$14,860

OR

Cary Rd- from Woods Ridge towards County D, stopping short of the intersection of Cty D

0.69 miles

Hot Mix Wedge both sides to fill in the ruts

Approximately 594 tons

\$70,300

If the Town would like to overlay the intersection, you either do the entire intersection or nothing at all on the intersection. Hot Mix

Approximately 88 tons

\$10,415

OR THE WORST OF THE ROAD

Cary Rd- from Woods Ridge going down thru the first dip to E10652

0.26 miles

Hot Mix Wedge both sides

Approximately 242 tons

\$28,460

Then skip the top of the hill where the road is OK, then

Cary Rd- starting at the windmill on the left going to the top of the hill

Hot Mix Wedge both sides

Approximately 154 tons

\$18,226

Then,

Cary Rd- top of the hill to County D

Hot Mix wedge just the right side of the road to D

Approximately 54 tons

\$6,391

TOWN OF CLINTON, VERNON COUNTY

4-5-24

2024 ROAD LIST

Chip Seal Coat using 3/8" Granite Chips

Knapp Valley Rd - from just below the Y intersection of Kelbel Rd going down the valley to just across the box culvert just past Easterdays

1.19 miles Single Seal Hard Surface \$31,578

Woods Ridge Rd- from the first corner off Cary Rd to County P

1.78 miles Single Seal Hard Surface \$47,234

Dell Rd- from S1676, just below the corner that was sealed in 2023 to the bridge by S1865

0.67 miles Single Seal Hard Surface \$16,890

Dell Rd- from the bridge by S1865 to County P

0.52 miles Single Seal Hard Surface \$13,799

Parker Rd- the section that is shared with the Town of Whitestown (1/2 is the Town of Clinton)

0.12 miles Single Seal Hard Surface \$3,503

Oneida Rd- from the Town of Jefferson line going up the hill to just below #31185/Amish Driveway on the right on the corner (wooded area)

0.26 miles Single Seal Hard Surface \$7,590

Oneida Rd- from just below #31185/Amish Driveway on the right on the corner going to the top of the hill to S203

0.17 miles Single Seal Hard Surface 8' Bar Seal east side only \$1,873

Olson Rd

Cristian

3000

63,200

OGDEN RD HOT MIX WEDING OPTIONS

Ogden Ave- from the new mat on the west end to the new mix on the east end
0.39 miles

Hot Mix Wedge both sides
Approximately 286 tons

\$33,848

OR THE WORST OF THE ROAD

Ogden Rd- from E9861 going down thru the dip to the top of the hill

Hot Mix wedge

From E9861 going down the hill, right side to Sharping Rd

From Sharping Rd, left side going up the hill ending just past phone
boot or E9921

Do nothing on the rest of the road to the top of the hill

Approximately 88 tons

\$10,415